



Central Purchasing

T. W. Sawyer, CPPO
Purchasing Agent

February 12, 2016

ADDENDUM NO. 3 - TO ALL OFFERORS
Reference Request for Proposals (RFP) No. 1980

Title QUEENS LAKE SANITARY SEWER PROJECT – CONTRACT #6 VACUUM LINEWORK
WEST

Dated: December, 2015

Due Date: February 17, 2016 at 2:00 pm

See attached six (6) pages.

All other terms and conditions remain the same.

Note: A signed acknowledgment of this addendum must be received by this office either prior to the due date or attached to your bid. Signature on this addendum does not constitute your signature on the original document. The original document must be signed also.

Sincerely,

T. W. Sawyer, CPPO, CPPB

Name of Firm

Signature/Title

Date



120 Alexander Hamilton Blvd. • PO Box 532 • Yorktown, Virginia 23690-0532 • (757) 890-3680

TDD (757) 890-3300

A Hampton Roads Community

Email: tsawyer@yorkcounty.gov



Addendum No. 3 – February 12, 2016

Queens Lake Sanitary Sewer Project Contract 6 – Vacuum Linework West

IFB No. 1980

This Addendum modifies the Contract Documents dated December 2015 as listed below, and is hereby incorporated into the Contract Documents. Bidder shall acknowledge receipt of this Addendum in the space provided on page 102-18 of the Bid Form. Failure to do so may subject Bidder to disqualification.

Project Manual Addendum Items

1. Section 02850, Prefabricated Steel Bridge, page 02850-1, Subsection 1.2 Paragraph C: ADD
 5. Excel Bridge Manufacturing Co.
320-762-1386

Drawing Addendum Items

2. Pertaining to Sheet S9, transverse bridge sections:
 - a. Center bolt though X-braces and blocking shall be ¾” diameter.
 - b. Blocking at X-brace may be:
 - i. Plies of 12” long 3x8s or 3x12s built up to match pile diameter (secure plies by nailing and bolt cross grain), or
 - ii. 8x8 cut to a length matching space between braces (bolt with grain)
 - c. Transverse blocking at posts is generally not shown this sheet. Provide 3x12 blocking/diaphragms at each post as indicated on framing plans S-7 and S-8.

Addendum Questions Submitted After Pre-Bid Meeting

3. Do you have a preferred provider for ductile iron pipe?
No. Bidders are advised to review Section 02700, Vacuum Sewer and Division Valves, Paragraph 2.1.A.2 as amended, for ductile iron pipe requirements.

End of Addendum.

III. BID FORM

Bids to be opened: **February 17, 2016**
 Work to be Completed in: **600 Days**
 Liquidated Damages: **\$500.00** per calendar day after time for Substantial Completion has expired.
\$500.00 per calendar day after time for Final Completion has expired.
 Performance Bond: 100%
 Payment Bond: 100%
 Bid Security: 5%

To: **County of York, Virginia**
120 Alexander Hamilton Drive
Yorktown, Virginia 23690
IFB No. 1980

A. BID PRICE

OPTION A - LUMP SUM BID (Unused)

OPTION B - COMBINATION LUMP SUM AND UNIT PRICE BID (Unused)

OPTION C - UNIT PRICE BID

In compliance with the Bid Documents, titled *Queens Lake Sanitary Sewer Project, Contract 6 – Vacuum Linework West, which incorporates the HRPDC Regional Construction Standards, Fifth Edition* all Addenda issued to date all of which are part of this Bid, the undersigned hereby proposes to furnish all items including materials, supervision, labor, and equipment in strict accordance with, said Contract Documents, for the sum of:

NO.	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
1	Mobilization, Complete (up to 5% of total price of all other base bid items)	LS	1		
2	Undercut Excavation with Bedding Backfill as Directed by Owner	CY	1000		
3	Select Material, Type II – Sand as Directed by Owner	Ton	12,000		
4	Select Material, Type II – Stone as Directed by Owner	Ton	12,000		
5	Miscellaneous Unclassified Excavation as Directed by Owner	CY	1000		
6	Silt Fence, Installed Complete-in-Place	LF	20,000		

NO.	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
7	Turbidity Curtain, Installed Complete-in-Place	LF	250		
8	Tree Protection, Installed Complete-in-Place	LF	2000		
9	Rock Check Dam, Installed Complete-in-Place	Each	10		
10	Aggregate Base Material, Complete-in-Place	Ton	10,000		
11	Prime Coat Over Trench Prior to Reconstruction, Complete-in-Place	LF	24,000		
12	Reconstructed Asphalt Pavement, Complete-in-Place	SY	51,500		
13	Concrete Driveway Restoration at Main Line or Lateral Crossing, Complete-in-Place	LF	220		
14	Exposed Aggregate Concrete Driveway Restoration at Main Line or Lateral Crossing, Complete-in-Place	LF	50		
15	Asphalt Driveway Restoration at Main Line or Lateral Crossing, Complete-in-Place	LF	340		
16	Aggregate Driveway Restoration, Complete-in-Place	Ton	900		
17	4" PVC Gravity Sewer Lateral, Installed Complete-in-Place	LF	2700		
18	4" PVC Gravity Sewer Lateral Cleanout Assembly, Installed Complete-in-Place	Each	212		
19	4" Gravity Sewer Lateral Backflow Preventer	Each	13		
20	1-1/2" PVC Force Main, Installed Complete-in-Place	LF	10,000		
21	2" PVC Force Main, Installed Complete-in-Place	LF	5200		
22	Horizontal Directional Drilling for Grinder Force Main	LF	800		
23	1-1/2" Grinder Force Main Cleanout and Valve Vault, Installed Complete in Place	Each	84		
24	2" Grinder Force Main Cleanout and Valve Vault, Installed Complete in Place	Each	1		
25	Low Pressure Force Main Cleanout/Air Relief Valve, Installed Complete-in-Place	Each	12		

NO.	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
26	2" Valve and Box Assembly, Installed Complete-in-Place	Each	8		
27	Grinder Pump Assembly, Model DH071-93, Installed Complete-in-Place	Each	62		
28	3" PVC Vacuum Sewer Lateral, Installed Complete-in-Place	LF	4500		
29	4" PVC Vacuum Sewer Lateral, Installed Complete-in-Place	LF	32		
30	4" PVC Vacuum Sewer Main, Installed Complete-in-Place	LF	3900		
31	6" PVC Vacuum Sewer Main, Installed Complete-in-Place	LF	2300		
32	8" PVC Vacuum Sewer Main, Installed Complete-in-Place	LF	7700		
33	8" DIP Vacuum Sewer Main, Installed Complete-in-Place	LF	770		
34	8" Expansion Flex-Tend Fitting, 40.4" Laying Length, Provided by Owner, Installed Complete-in-Place	Each	1		
35	8" Expansion Flex-Tend Fitting, 57.5" Laying Length, Provided by Owner, Installed Complete-in-Place	Each	1		
36	Stainless Steel Pipe Saddle, Installed Complete-in-Place	Each	45		
37	4" Vacuum Sewer Division Valve and Gauge Tap Assembly, Installed Complete-in-Place	Each	8		
38	6" Vacuum Sewer Division Valve and Gauge Tap Assembly, Installed Complete-in-Place	Each	4		
39	8" Vacuum Sewer Division Valve and Gauge Tap Assembly, Installed Complete-in-Place	Each	9		
40	End of Line Marker, Installed Complete-in-Place	Each	17		
41	STD 6 FT Vacuum Valve Pit, Installed Complete-in-Place	Each	35		
42	DEEP 8 FT Vacuum Valve Pit, Installed Complete-in-Place	Each	23		
43	XDP 9 FT Vacuum Valve Pit, Installed Complete-in-Place	Each	20		

NO.	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
44	Vacuum Buffer Tank, Installed Complete-in-Place	Each	3		
45	Appurtenances for Valve Pit with EAAC, Installed Complete-in-Place	Each	3		
46	PVC Air Intake for Grinder Force Main Connection to Valve Pit, Installed Complete-in-Place	Each	8		
47	Tracer Wire Box, Installed Complete-in-Place	Each	10		
48	6" DI Casing Pipe, Installed Complete-in-Place	LF	200		
49	8" DI Casing Pipe, Installed Complete-in-Place	LF	100		
50	12" DI Casing Pipe, Installed Complete-in-Place	LF	100		
51	Vacuum Sewer Line Flushing and Testing	LS	1		
52	Heat Tracing System, Installed Complete-in-Place	LS	1		
53	1" PVC Electrical Conduit, Installed Complete-in-Place	LS	1		
54	Heat Trace Power Cable, Installed Complete-in-Place	LS	1		
55	Pipe/Pedestrian Bridge, Installed Complete-in-Place	LS	1		
56	Retaining Walls, Installed Complete-in-Place	LS	1		
57	5' Concrete Walk with 4" Aggregate Base Course, Installed Complete-in-Place	SY	50		
58	Concrete Walk at Western Bridge Abutment, Installed Complete-in-Place	LS	1		
59	Stainless Steel Bollard, Installed Complete-in-Place	Each	2		
60	Test Piles	LF	385		
61	Production Piles, Installed Complete-in-Place	LF	3840		
62	Site Grading from Bridge to Pump Station, Complete	LS	1		

NO.	ITEM	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
63	Relocation of Active Water Line	LS	1		
				Total	

Bidder acknowledges that estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all Unit Price Bid items will be based on actual quantities provided, determined as provided in the Contract Documents. The prices quoted shall include without exception all materials, supervision, labor, equipment, appliances, clean-up, incidental items, applicable sales, use and other taxes, insurance, building permit or fees, and the Contractor's labor, overhead, profit, mobilization and other mark-ups, and in full accordance with the Contract Documents. Include allowance for waste where appropriate. The unit prices shall be maintained throughout the Contract Time. Unit prices shall be used in determining additions or deductions from the total Contract Price in the event of changes due to unforeseen conditions in the Work.

B. ADDENDA

The undersigned acknowledges receipt of the following addenda:

Addendum No. _____ 1 _____ Dated: February 8 9, 2016.

Addendum No. _____ 2 _____ Dated: February 11, 2016.

Addendum No. _____ 3 _____ Dated: February 12, 2016.

- C. We agree to enter into an Agreement with the **County of York**, Virginia within ten (10) days of the award of same to us for the price named in our Bid.
- D. It is expressly agreed by us that the **County of York**, Virginia shall have the right to reject any and all Bids and to waive any minor non-substantive errors in the Bid and accept the Bid in the **County of York's** best interests.
- E. In default of the performance on our part of the conditions of Bid, our failure to enter into an Agreement with the **County of York**, Virginia, within the time above set, we herewith furnish a Bid Security in the amount of \$_____, which shall be absolutely forfeited to the **County of York**, Virginia, but otherwise the said Bid Security shall be returned.
- F. We agree to begin Work at any time we may be notified by the Owner, and complete all of the Work embraced in the Agreement within **600** Days;
- G. I/We elect to utilize the Escrow Account Procedure described in the provision of this bid if determined to be the successful low Bidder. _____ (write "Yes" or "No").
_____ Bid total does not qualify for escrow account option
- H. The undersigned has read all sections under "Instructions to Bidders."
- I. By signing, each signatory acknowledges any strike-throughs contained herein, unless hand-written.

