



YORK COUNTY
DEPARTMENT OF PUBLIC WORKS
STORMWATER PROGRAMS

Stormwater As-built Review Checklist

Name of Project _____ **Date** _____

- 1) Record Drawings are required for all components of the stormwater system. The record drawings shall be appropriately sealed and signed by a licensed professional in adherence to all minimum standards and requirements pertaining to the practice of that profession. See section 23.3-18 of County Code. The record drawings shall:
 - Be of the same sheet size; format, scale, etc. as the approved stormwater management plans;
 - Show the as-built condition of the stormwater system calling attention to any changes from the approved drawings;
 - Give the actual dimensions of components such as length of pipe, ditch, etc.;
 - Provide elevations for all rims, inverts, channel bottoms, outfalls, pond cross-sections, structures and all other elevation sensitive components of the system;
 - Provide details for all BMP's to include inverts, depth, structures and any other associated details;
 - Have lot lines, numbers, street names and Easement Information
 - Benchmark with description.
 - Maintenance information should also be provided on plan; and
 - Contain a Certification statement by professional engineer or surveyor that all drainage facilities have been installed in accordance with the design, the system is functioning as designed, and that information provided has been field verified.

Pursuant to 9VAC25-870-55, I hereby certify that, to the best of my knowledge and belief, the stormwater management facilities shown on these record drawings have been constructed in accordance with the approved plans and specifications.

Name

Signature

Virginia License

Date